

SECTION 00310 - BID SCHEDULE

BASE BID

Pay Item No.	Pay Item Description	Pay Unit	Approximate Quantity	Unit Price		Amount	
				Dollars	Cents	Dollars	Cents
1505.1	Mobilization	LS	All Req'd	X	X	3,855,000	—
1570.1	Erosion and Sediment Control	LS	All Req'd	X	X	41,000	—
1580.1	Contaminated Materials Removal	CY	100	720	—	72,000	—
2060.1	Demolition and Disposal	LS	All Req'd	X	X	793,000	—
2202.1	Class A Shot Rock Borrow	CY	500	175	—	87,500	—
2202.2	Class B Shot Rock Borrow	CY	4,000	165	—	660,000	—
2204.1	Base Course, Grading D-1	CY	350	188	—	65,800	—
2205.1	Armor Rock, Class III	CY	1500	570	—	855,000	—
2205.2	Shoulder Barrier Rock	EA	34	3,215	—	109,810	—
2401.1	Sanitary Sewer Service	LS	All Req'd	X	X	140,000	—
2501.1	4-Inch PVC Storm Drain Pipe	LF	66	172	—	11,352	—
2501.2	12-Inch CPP Storm Drain Pipe	LF	134	432	—	57,888	—
2501.3	18-Inch CPP Storm Drain Pipe	LF	44	532	—	23,408	—
2502.1	Storm Drain Catch Basin, Type IV	EA	1	23,500	—	23,500	—
2502.2	Oil Water Separator	EA	2	36,000	—	72,000	—
2502.3	Storm Drain Outfall Structure, Type I	EA	2	93,700	—	187,400	—
2502.4	Storm Drain Outfall Structure, Type II	EA	4	21,300	—	85,200	—
2601.1	Domestic Water System	LS	All Req'd	X	X	891,000	—
2611.1	Fire Suppression System	LS	All Req'd	X	X	254,000	—
2702.1	Construction Surveying	LS	All Req'd	X	X	166,000	—
2714.1	Geotextile Filter Cloth	SY	800	30	—	24,000	—
2718.1	Sign Assembly	LS	All Req'd	X	X	32,500	—
2882.1	Contingent Work – Pile Obstruction Removal	CS	All Req'd	X	X	75,000	00

SECTION 00310 - BID SCHEDULE

BASE BID

Pay Item No.	Pay Item Description	Pay Unit	Approximate Quantity	Unit Price		Amount	
				Dollars	Cents	Dollars	Cents
2894.1	Aluminum Gangway, 6' x 80'	LS	All Req'd	X	X	100,000	-
2895.1	Gangway Landing Float, 24' x 20'	LS	All Req'd	X	X	404,000	-
2895.2	Headwalk Float, 10' x 254'	LS	All Req'd	X	X	1,500,000	-
2895.3	Mainwalk Float A, 10' x 282'	LS	All Req'd	X	X	1,595,000	-
2895.4	Mainwalk Float B, 16' x 240'	LS	All Req'd	X	X	2,134,000	-
2895.5	Finger Float, 6' x 42'	EA	5	140,000	-	700,000	-
2895.6	Finger Float, 4' x 32'	EA	6	91,800	-	550,800	-
2895.7	Finger Float, 4' x 26'	EA	7	75,000	-	525,000	-
2895.8	Final Design of Moorage Floats	LS	All Req'd	X	X	163,000	-
2896.1	Furnish Steel Pipe Pile, 24" x 0.500"	LF	3,790	300	-	1,137,000	-
2896.2	Install Pile with Shoe in Drilled Socket	EA	42	40,500	-	1,701,000	-
2896.3	Pile Mooring Frame	EA	7	44,000	-	308,000	-
2899.1	Life Ring Cabinet and Base	EA	5	3,000	-	15,000	-
2899.2	Fire Extinguisher Cabinet and Base	EA	5	3,000	-	16,000	-
2899.3	Fixed Safety Ladder	EA	4	5,000	-	20,000	-
2899.4	Deployable Safety Ladder	EA	3	3,500	-	10,500	-
2996.1	Supply Pile Anode	EA	67	1,150	-	77,050	-
2996.2	Install Pile Anode	EA	160	1,900	-	304,000	-
2996.3	Anode Continuity Testing	LS	All Req'd	X	X	43,000	-
3303.1	Concrete Seawalk	SY	75	975	-	73,125	-
3303.2	Curb and Gutter	LF	80	290	-	23,200	-
3303.3	Concrete Area Drain	LS	All Req'd	X	X	10,000	-
3305.1	Concrete Abutment	LS	All Req'd	X	X	750,000	-

SECTION 00310 - BID SCHEDULE

BASE BID

Pay Item No.	Pay Item Description	Pay Unit	Approximate Quantity	Unit Price		Amount	
				Dollars	Cents	Dollars	Cents
5120.1	Abutment Safety Rail	LS	All Req'd	X	X	53,000	—
13100.1	Restroom	LS	All Req'd	X	X	575,000	—
16000.1	Electrical and Lighting System	LS	All Req'd	X	X	2,965,000	—
16000.2	Electrical Support Assemblies	LS	All Req'd	X	X	465,000	—

TOTAL BASE BID AMOUNT IN FIGURES: \$ 24,796,533.⁰⁰

TOTAL BASE BID AMOUNT IN WORDS:

TWENTY FOUR MILLION SEVEN HUNDRED NINETY SIX THOUSAND FIVE HUNDRED THIRTY THREE

COMPANY NAME: Duwamish Services LLC

END OF SECTION